ervia

European Commission

ERVIA CCS PRE-FEED STUDY

Study Basis - Cork

MDE1234-RPS-01-CX-RP-Z-0001
S3 P03
05 April 2022

rpsgroup.com

rps BECHTEL

Document status

Status	Revision	Purpose of document	Authored by	Reviewed by	Approved by	Review date
S3	P01	Issue for Review & Comment	PD / RK / GR	MJC / CB / PD	CB	29/09/2021
S3	P02	Updated with Ervia Feedback	PD / RK / GR	MJC / CB / PD	CB	15/12/2021
S3	P03	Issued for Pre-FEED	PD / RK / GR	MJC / CB / PD	CB	30/03/2022

Approval for issue

CB 5 April 2022

© Copyright RPS Group Limited. All rights reserved.

The report has been prepared for the exclusive use of our client and unless otherwise agreed in writing by RPS Group Limited no other party may use, make use of or rely on the contents of this report.

The report has been compiled using the resources agreed with the client and in accordance with the scope of work agreed with the client. No liability is accepted by RPS Group Limited for any use of this report, other than the purpose for which it was prepared.

RPS Group Limited accepts no responsibility for any documents or information supplied to RPS Group Limited by others and no legal liability arising from the use by others of opinions or data contained in this report. It is expressly stated that no independent verification of any documents or information supplied by others has been made.

RPS Group Limited has used reasonable skill, care and diligence in compiling this report and no warranty is provided as to the report's accuracy.

No part of this report may be copied or reproduced, by any means, without the written permission of RPS Group Limited.

Prepared by:

RPS / Bechtel

Prepared for:

Ervia

Dublin | Cork | Galway | Sligo
rpsgroup.com

RPS Group Limited, registered in Ireland No. 91911
RPS Consulting Engineers Limited, registered in Ireland No. 161581
RPS Planning & Environment Limited, registered in Ireland No. 160191
RPS Engineering Services Limited, registered in Ireland No. 99795
The Registered office of each of the above companies is West Pier Business Campus, Dun Laoghaire, Co. Dublin, A96 N6T7

Contents

Holds iv
Glossary v
References vi

1 INTRODUCTION AND SCOPE 1
1.1 Project Background 1
1.2 Scope 1

2 APPLICABLE REGULATIONS AND STANDARDS 2

3 UNITS OF MEASUREMENT 3

4 BASIS OF DESIGN 4
4.1 Design Capacity 4
4.2 Onstream Factor 4
4.3 Turndown Requirements 4
4.4 CO_2 Source Flowrates 4
4.5 Project Phases 5
4.6 CO_2 Specification from Source 5
4.7 CO_2 Specification for Pipeline 6
4.8 CO_2 Conditions at Emitter Battery Limit (CPF) 7
4.9 CO_2 Delivery Specification 7
4.10 CO_2 Delivery Conditions 8
4.11 Pipeline Conditions from Emitters to CPF 9
4.12 Pipeline Conditions from CPF to Inch Terminal (Existing) 9
4.13 Metering and Monitoring of CO_2 10
4.14 Meteorological Data 10
4.14.1 Temperature 10
4.14.2 Atmospheric Pressure 11
4.14.3 Humidity 11
4.14.4 Rainfall 11
4.15 Wind Data 12
4.16 Seismic Data 12
4.17 Snow Data 13
4.18 Ice Data 13
4.19 Metocean Data 14
4.20 CO_2 Transport and Storage Infrastructure 14

5 PHILOSOPHY DOCUMENTS 16

Tables

Table 4-1 CO_2 Flowrates from Source, MMtpa 4
Table 4-2 Project Phases 5
Table 4-3 CO_2 Specification from Source/Emitters 5
Table 4-4 CO_2 Pipeline Design Specification 6
Table 4-5 CO_2 Conditions at Emitter Battery Limit 7
Table 4-6 CO_2 Delivery Specification 7
Table 4-7 CO_2 Ship Transport Conditions 8
Table 4-8 Pipeline Conditions from Emitters to CPF 9
Table 4-9 Inch to Caherlag Pipeline BGE/01 Conditions 9
Table 4-10 Temperatures for use in Design 10
Table 4-11 Sea Water Supply and Return Temperature for Regasification for use in Design 11

Table 4-12 Atmospheric Pressure[1] 11
Table 4-13 Humidity[1] 11
Table 4-14 Rainfall Data for use in Design 11
Table 4-15 Rainfall Intensity for use in Design 12
Table 4-16 Wind Speeds for use in Design* 12
Table 4-17 Snow Data 13
Table 4-18 Tide Levels 14
Table 4-19 Ship Data 15

Appendices

Appendix A Units of Measurement

Holds

HOLDS	Description	Responsibility

Glossary

Term	Definition
AACE	Association for the Advancement of Cost Engineering
CCGT	Combined Cycle Gas Turbine
CPF	Central Processing Facility
CCS	Carbon Capture and Storage
FEED	Front End Engineering Design
MMtpa	Million Metric Tonnes Per Annum

References

1. Cork CCS Project Option Site Specific Case Study, 267553-REP-001, Issue 04, 16 Dec 2020
2. Ashrae Handbook- Fundamentals (SI) (2017)- Roches Point, Ireland (WMO:039520). Available from- ASHRAE climatic design conditions 2009/2013/2017 (ashrae-meteo.info) [Accessed on 09/09/2021]
3. Ashrae Handbook (2009), Appendix- Design Conditions for Selected Locations. Available from- https://www.captiveaire.com/catalogcontent/fans/sup_mpu/doc/winter_summer_design_temps_us.pdf [Accessed on-13/09/2021]
4. EPA IPC Reg. No. 576 Proposed Determination for Electricity Supply Board Aghada Generating Station Whitegate, County Cork (2002). Available from- Microsoft Word - 576TCReport.doc (epa.ie) [Accessed on 20/09/2021]
5. Met Éireann Return Period Rainfall Depths for sliding Durations based on Depth Duration Frequency (DDF) Model - Fitzgerald D. L. (2007), Estimates of Point Rainfall Frequencies, Technical Note No. 61, Met Eireann. Available from- Services - Met Éireann - The Irish Meteorological Service [Accessed on 9/9/2021]
6. Eurocode 1: Actions on structures - Part 1-4: General actions - Wind actions, I.S. EN 1991-1-4:2005+NA:2013 (2005). Available from- 98705226958.pdf (standards.ie) [Accessed on 16/09/2021]
7. Eurocode 1 - Actions on structures. General actions - Snow loads (+AC:2009) (+A1:2015). I.S. EN 1991-1 -3:2003&A1:2015 (2010). Available from- 753181013011.pdf (standards.ie) [Accessed on 16/09/2021]
8. Eurocode 8: Design of structures for earthquake resistance - Part 1: General rules, seismic actions and rules for buildings, I.S. EN 1998-1:2005 (2004). Available from- 98700969003.pdf (standards.ie) [Accessed on 16/09/2021]
9. UK Hydrographic Office-Admiralty Tide Tables, United Kingdom and Ireland, NP201B, Volume 1B (2021). [Accessed on 24/09/2021]
10. Electricity Supply Board Aghada Combined Cycle Gas Turbine Power Plant Environment Impact Statement July 2004 Report P378250R6050001 [Accessed on 28/09/2021]
11. Operations and Maintenance, MDE1234-RPS-01-CX-RP-Z-0010

1 INTRODUCTION AND SCOPE

1.1 Project Background

Ervia is assessing how Carbon Capture and Storage (CCS), located close to large-scale CO_2 emitters can play a role in reducing Ireland's CO_2 emissions. A technical feasibility study on the potential for large-scale CCS in Ireland was completed by Ervia in 2020.

The general location of Aghada Power Station in County Cork was selected as a potential site for a Central Processing Facility (CPF) for liquefaction, storage, and export of CO_2 overseas via a new marine jetty. The CPF will cater for CO_2 captured at 3 emitter locations (Whitegate Power Station, Irving Oil Whitegate Refinery and Aghada CCGT). A new CO_2 gas pipeline gathering network will transport CO_2 from the emitters to the CPF.

Ervia has appointed RPS / Bechtel to carry out a Pre-FEED study that involves a detailed assessment of the key CPF, pipeline and storage infrastructure necessary to condition, compress, transport and store liquid CO_2 at Cork harbour for subsequent loading onto ships for export. (Note: The scope of this project does not include the carbon capture facilities at each emitter).

Additionally, the new marine jetty in Cork will also be used for import of liquid CO_2. This scenario considers the regasification of liquid CO_2 at Cork for transport via pipeline to the Inch terminal which is the link to indigenous offshore permanent storage at the depleted Kinsale Head Gas Field.

1.2 Scope

This document sets out the basis of design for executing the pre-FEED study for CO_2 transport from emitter sites to storage and the marine jetty for ship transport from Cork. The study will also address the importation of liquid CO_2 from other sources for pipeline transfer to indigenous storage.

The process of CO_2 capture at emitter sites is excluded from the pre-FEED study. It is considered that the CO_2 from the capture plants is conditioned, and meets the specification specified in Table 4-3. The CPF process will consist of only refrigeration and liquefaction.

The regasification of CO_2 in Cork is included in the pre-FEED study. It is to be assumed that the regasification plant will take advantage of the seawater from the existing Aghada CCGT plant outlet for the vapourisation process.

An AACE Class 4 estimate will be developed as part of pre-FEED study.

Project co-ordinates will be developed as part of pre-FEED study.

2 APPLICABLE REGULATIONS AND STANDARDS

In the event of conflict or deviation from requirements stipulated in this design basis and other applicable documents, the following order of precedence shall govern:

- European Regulations
- Irish Regulations
- European Standards
- International Standards
- Irish Standards
- Ervia Standards

A preliminary list of regulations and standards will be developed as part of pre-FEED scope as a basis for FEED.

3 UNITS OF MEASUREMENT

SI measuring units as shown in Appendix A of this document will be followed.

4 BASIS OF DESIGN

4.1 Design Capacity

The design capacity of each liquefaction train shall be 0.44 MMtpa CO_2. There will be 4 liquefaction trains of 0.44 MMtpa each (3 operating and 1 standby).

The design capacity of the regasification train shall be 0.5 MMtpa CO_2. There will be one regasification train of 0.5 MMtpa .

It is considered that the liquefaction and regasification trains will not be operating simultaneously (i.e. plant will either be in liquefaction or regasification mode).

4.2 Onstream Factor

Each of the four liquefaction trains shall be designed for 350 operating days (8,400 hours) per year. The design life of the new CPF shall be 25 years, i.e. the design shall be such that the train will be able to operate at 100% of design feed throughput for 25 years, with inspection turnarounds occurring every 4 years.

The design life of new pipeline will nominally be 40 years.

4.3 Turndown Requirements

The design shall be such that each train will be able to operate at 0.125MMtpa CO_2 which is 50% of maximum flowrate from the lowest emitter i.e. Whitegate Refinery.

4.4 CO_2 Source Flowrates

Whitegate Refinery, Aghada CCGT and Whitegate CCGT are the three CO_2 emitters considered for the pre-FEED study scope for CO_2 transport, storage and shipping of CO_2 from Cork. Refer to Table 4.1 for CO_2 flowrates from emitters:

Table 4-1 CO_2 Flowrates from Source, MMtpa

Source	CO_2 Flowrates from Source MMtpa		
	Max/Min Year 1	Max/Min Year 2	Max/Min Year 3
Whitegate Refinery	0.25/0.125	0.25/0.125	0.25/0.125
Aghada CCGT	-	0.5/0.25	0.5/0.25
Whitegate CCGT	-	-	0.5/0.25
Total (Max/Min)			1.25/0.125

Notes:
1. *Minimum total CO_2 flowrate considered to be 0.125 MMtpa (50% of maximum flowrate from lowest emitter i.e. Whitegate Refinery).*

4.5 Project Phases

There are four phases of the project, refer to Table 4.2 for details of different phases of project and pre-FEED scope.

Table 4-2 Project Phases

Project Phase	Description
1	CO_2 from Cork and liquefaction and export via new jetty
2	Import of liquified CO_2 and export via new jetty
3	Cork gaseous CO_2 is sent to Inch Terminal for sequestration
4	Imported liquid CO_2 is re-gasified in Cork and sent to Inch Terminal

4.6 CO_2 Specification from Source

The quality of CO_2 produced by emitters is very important as it relates to integrity of the transport and storage system. It is considered that CO_2 from capture plant is conditioned, and no further treatment of CO_2 has been considered as part of pre-FEED scope. Dehydration is required at the capture plant to ensure dry CO_2 enters the pipeline. Oxygen removal to achieve the oxygen specifications is by catalytic reaction with injected hydrogen, which generates water and shall be located upstream of the dehydration i.e. also included in the capture unit. As the optimum conditions for dehydration and oxygen removal is at 30-40bara, the expected delivery pressure from the capture unit is expected to be at 35bara. The specification of CO_2 from emitters is governed by the specification provided by Equinor to Ervia for the purposes of shipping and sequestration. Refer to Table 4.3 for CO_2 specification from emitters.

Table 4-3 CO_2 Specification from Source/Emitters

Component	Recommended Specification
CO_2	>99.97 mol%
H_2S	<9 ppmv
Carbon Monoxide	<100 ppmv
NOx	<10 ppmv
SO_X	<10 ppmv
Oxygen	<10 ppmv
Nitrogen	-
Hydrogen	<50 ppmv
Argon	-
Methane	-
Non-condensable	-
Water	<30 ppmv
Hydrocarbon	-

Component	Recommended Specification
Particulates	1 mg/Nm^3
Particle size	≤10µm
Mercury	<0.03 ppmv
NH_3	<10 ppmv
Others	Amine <10 ppmv Formaldehyde <20ppmv Acetaldehyde <20pmv Cd+Tl <0.03 ppmv

Note: CO_2 specification is related to gaseous phase CO_2.

4.7 CO_2 Specification for Pipeline

CO_2 pipeline to be designed for most stringent of Acorn and Equinor specifications. As agreed with Ervia, the specification of exported CO2 for the Equinor's Northern Lights project and Acorn is as specified in Table 4.4:

Table 4-4 CO_2 Pipeline Design Specification

Component	Equinor Specification	Acorn Specification
CO_2	>99.97 mol%	≥ 95 mol%
H_2S	<9 ppmv	< 200 ppmv
Carbon Monoxide	<100 ppmv	<2000 ppmv
NOx	<10 ppmv	<100 ppmv
SO_X	<10 ppmv	<100 ppmv
Oxygen	<10 ppmv	<10 ppmv
Nitrogen	-	≤1 mol%
Hydrogen	<50 ppmv	≤1 mol%
Argon	-	≤1 mol%
Methane	-	≤1 mol%
Non-condensable	-	≤ 4 mol%
Water	<30 ppmv	≤ 50 ppmv
Hydrocarbon	-	≤ 2 mol%
Particulates	1 mg/Nm^3	<1 mg/Nm^3
Particle size	≤10µm	≤10µm
Mercury	<0.03 ppmv	
NH_3	<10 ppmv	< 50 ppmv
Others	Amine <10 ppmv	

Component	Equinor Specification	Acorn Specification
	Formaldehyde <20ppmv Acetaldehyde <20pmv Cadmium+Thallium (Cd+Tl) <0.03 ppmv	

Note: Equinor and Acorn specifications are related to gaseous phase CO_2.

4.8 CO_2 Conditions at Emitter Battery Limit (CPF)

CO_2 emitters shall ensure that operating pressure and temperature of CO_2 at emitter battery limit will be as provided in Table 4.5.

Table 4-5 CO_2 Conditions at Emitter Battery Limit

Parameter	Whitegate Refinery	Aghada CCGT	Whitegate CCGT
Pressure, bara	35	35	35
Temperature Min/Max, °C [1]	11/37	11/37	11/37

[1] CO_2 cooling by emitters can be by sea water, cooling water or air. Depending upon the cooling medium, CO_2 temperature at emitter battery limit can be:

- *Sea water: Min = winter sea temp +5°C approach, Max = summer sea temperature +10°C approach*
- *Cooling tower water: Max = max design wet bulb temperature + 5°C+ 10°C*
- *Air cooling: Max = max design dry bulb temperature + 15°C*

4.9 CO_2 Delivery Specification

CO_2 delivery specification for project will be the most stringent of Equinor and Acorn specifications.

Refer to Table 4.6 for export CO_2 specification:

Table 4-6 CO_2 Delivery Specification

Component	Recommended Specification
CO_2	>99.97 mol%
H_2S	<9 ppmv
Carbon Monoxide	<100 ppmv
NOx	<10 ppmv
SO_X	<10 ppmv
Oxygen	<10 ppmv
Nitrogen	-
Hydrogen	<50 ppmv

Component	Recommended Specification
Argon	-
Methane	-
Non-condensable	-
Water	<30 ppmv
Hydrocarbon	-
Particulates	1 mg/Nm^3
Particle size	≤10µm
Mercury	<0.03 ppmv
NH_3	<10 ppmv
Others	Amine <10 ppmv Formaldehyde <20ppmv Acetaldehyde <20pmv Cd+Tl <0.03 ppmv

Note: CO_2 specification is related to gaseous phase CO_2.

4.10 CO_2 Delivery Conditions

CO_2 transport by ship is achieved in semi pressurised vessels at medium pressure conditions. Existing CO_2 carriers operate under medium pressure conditions which maintain the CO_2 between 14 bara to 20 bara at equilibrium temperature. Refer to Table 4.7 for CO_2 ship transport conditions.

Table 4-7 CO_2 Ship Transport Conditions

Parameter	Ship Transport Conditions Range (Medium Pressure Conditions)
Pressure, bara (Min/Max)	14 / 20
Temperature, °C (Min/Max)	-30 / -19.5

4.11 Pipeline Conditions from Emitters to CPF

Gaseous CO_2 will be transported from emitters using pipeline to CPF. The gaseous CO_2 pipeline conditions from emitters to CPF are as specified in Table 4.8:

Table 4-8 Pipeline Conditions from Emitters to CPF

Parameter	Pipeline Section 1 White Gate Refinery	Pipeline Section 2 White Gate CCGT	Pipeline Section 3 Aghada CCGT
Minimum Gas Capacity, MMtpa	0.125	0.25	0.25
Maximum Gas Capacity, MMtpa	0.25	0.5	0.5
Pipeline Inlet Temperature (Min/Max), °C	11/37	11/37	11/37
Pipeline Arrival Temperature[1] (Min/Max), °C	10/27	10/27	10/27
Pipeline Inlet Pressure, bara	35	35	35
Pipeline Arrival Pressure[1], bara	32.5	32.5	32.5
Pipeline Design Temperature[1], °C	70	70	70
Pipeline Design Pressure[1], bara	40	40	40

[1] Flow assurance to provide preliminary values for the study and final values will be confirmed for FEED.

4.12 Pipeline Conditions from CPF to Inch Terminal (Existing)

Project Phase 3 assumes existing 24" export pipeline to Kinsale Head Gas Field would be potentially reused for transporting CO_2 to permanent storage at Kinsale Head Gas Field offshore. BGE/02 pipeline from Longpoint AGI to the Whitegate AGI and Whitegate AGI to Ardrabeg AGI is not available for CO_2 transport.

The existing natural gas pipeline which is available to the project is to be analysed for conversion to CO_2 transportation. The existing pipeline details are summarised on Table 4.9 below.

Table 4-9 Inch to Caherlag Pipeline BGE/01 Conditions

Parameter	Pipeline BGE/01 Inch to Caherlag Pipeline *(Ardrabeg AGI to Inch AGI)*
Year of Construction	1977
Nominal Diameter, mm	600
Outside Diameter, mm	609.6
Wall Thickness, mm	9.52/14.27
Pipeline Length, m	2162.37
Material	Steel
Material Specification	API 5L X52
External Coating	Coal Tar
Maximum Operating Pressure, bara	37.5/70
Rated Design Pressure, bara	70

4.13 Metering and Monitoring of CO_2

Custody metering and quality monitoring of CO_2 will take place at emitter sites.

Emitters shall share the CO_2 quality and metering data with Ervia control centre in Cork. Emitters shall also share calibration records of CO_2 metering and quality monitoring instruments and analysers with Ervia. The emitter shall inform the Operator at the CPF immediately if there is any deviation in quality of CO_2. Emitters shall immediately close the isolation valves at their facility if there is any deviation in quality of CO_2.

If the CPF Operator determines that the quality of CO_2 entering the gathering network is out of specification (either by own analysis results or analysis results provided by the emitter), the CPF Operator should inform Operator at emitters site so that Operator at emitters site can shut the pipeline operations. Provision is also provided for CPF Operator to initiate remote shutting of pipeline valves using motor operated valves. This action will contain the out of specification CO_2 to the pipeline. The above measures will protect the CPF from out of specification CO_2. The out of specification CO_2 in the pipeline can be depressurised using depressurisation valve. Venting of out of specification CO_2 will be at the emitter sites. Refer Operations and Maintenance Philosophy (Ref. #11) for more details.

Metering and quality monitoring of stored CO_2 will be provided for CO_2 that will be exported from Cork CPF via ship.

4.14 Meteorological Data

4.14.1 Temperature

Table 4-10 Temperatures for use in Design

Parameter	Value
Design Maximum Dry Bulb Temperature (DBT), ºC (n=20) [1]	28 ºC[2]
Design Maximum Wet Bulb Temperature (WBT), ºC (n=20) [1]	21 ºC[2]
Design Maximum DBT for Air Coolers, ºC	22 ºC[3]
Sea Water Summer (Maximum) Temperature, ºC	19 ºC[4]
Sea Water Winter (Minimum) Temperature, ºC	6 ºC[4]
Design Maximum Temperature for Outdoor Electrical Equipment, ºC	Equipment specific
Design Maximum Temperature for Indoor Electrical Equipment, ºC	Equipment specific
Design Maximum Temperature for Electrical Lighting Fittings, ºC	Equipment specific
Design Maximum Temperature for Surfaces exposed to Solar Radiation, ºC	Equipment specific
Winterising (Minimum) Temperature for pour point and freeze protection, ºC	Equipment specific
Low Ambient Temperature, ºC (n=20) [1]	-3.8 ºC[2]
Low Ambient Design Temperature, ºC	-12.5 ºC[5]

[1] *n= Year Return Period Values of Extreme Temperature*

[2] *ASHRAE CLIMATIC DESIGN CONDITIONS 2017*

[3] *ASHRAE 2009*

[4] *ESB-EIS, July 2004, Report P378250-R605-0001- https://www.eib.org/attachments/pipeline/20070106_eia_en.pdf*

[5] *Design Assumption*

Table 4-11 Sea Water Supply and Return Temperature for Regasification for use in Design

Parameter	Value[1]	
	Maximum	Minimum
Sea Water Temperature for Regasification (Inlet), ºC	32	11.4
Sea Water Temperature for Regasification (Outlet)[2], ºC	19	5

1.Sea water supply and return temperature from EPA IPC Reg. No. 576 Proposed Determination: https://epawebapp.epa.ie/licences/lic_eDMS/090151b2800bff3c.pdf

2. Sea Water Outlet Temperature for regasification to be confirmed during FEED.

4.14.2 Atmospheric Pressure

Table 4-12 Atmospheric Pressure[1]

Parameter	Value
Minimum, bara	1
Normal / Average, bara	1.013
Maximum, bara	1.024

[1]World Weather Online- Whitegate Cork- https://www.worldweatheronline.com/whitegate-weather-history/cork/ie.aspx

4.14.3 Humidity

Table 4-13 Humidity[1]

Parameter	Value
Minimum, %	82%
Maximum, %	89%

[1]World Weather Online- Whitegate Cork- https://www.worldweatheronline.com/whitegate-weather-history/cork/ie.aspx

4.14.4 Rainfall

Table 4-14 Rainfall Data for use in Design

Parameter	Value
Average Annual Rainfall[1], mm	945 mm
Design Rainfall in 15 min[2], mm per annum	6.7 mm
Design Rainfall in 24 h[2], mm per annum	38.4 mm
Design Rainfall in 48 h[2], mm per annum	48.7 mm

[1] ASHRAE CLIMATIC DESIGN CONDITIONS 2017
[2] Met Éireann Return Period Rainfall Depths for sliding Durations

Table 4-15 Rainfall Intensity for use in Design

Duration	Rainfall Intensity (mm/hr) *				
	2yr ARI	5yr ARI	10yr ARI	30yr ARI	100yr ARI
10 min	6.5	9.3	11.5	15.5	21.2
15 min	7.7	11	13.5	18.2	25
30 min	10	14	17.1	22.8	30.9
1 h	12.9	17.9	21.7	28.6	38.2
24 h	42.5	55.2	64.3	80.1	100.9

** Met Éireann- Return Period Rainfall Depths for sliding Durations*

4.15 Wind Data

I.S. EN 1991-1-4:2005+NA:2013 "Eurocode 1: Actions on structures – Part 1-4: General actions – Wind actions (Including Irish National Annex)" provides details on appropriate wind loading as follows:

Table 4-16 Wind Speeds for use in Design*

Parameter	Value
Fundamental basic wind speed velocity (V_{bmap})	25.8
Distance upwind to shoreline (L_{shore})	0
Altitude above sea level (C_{alt})	0
Direction Factor (C_{dir})	1
Season Factor (C_{season})	1
Shape parameter for probability factor (K)	0.2
Exponent for probability factor (n)	0.5
Annual probability of exceedance (p)	1 in 50 Years
Orthography type	N/A
Terrain category	Sea

Notes:
** Eurocode 1 – Actions on Structures – Part 1-4 General Actions – Wind Actions*

4.16 Seismic Data

I.S. EN 1998-1:2004 "Eurocode 8: Design of structures for earthquake resistance – Part 1: General rules, seismic actions and rules for buildings" states the following:

> *"Following established engineering practice, all of the Republic of Ireland is deemed to be in an area of very low seismicity and as such national annexes are not considered necessary for adopted EN 1998 parts".*

On the basis of the above, the consideration of seismic factors is not a design requirement for the project.

4.17 Snow Data

IS EN 1991-1-3:2003 “Eurocode 1 - Actions on structures. General actions - Snow loads (+AC:2009) (+A1:2015) provides details on snow loading that should be used as follows:

Table 4-17 Snow Data

Parameter	Value
Altitude	0
Ground Snow Load kN/m2	0.6
Topography	Normal
Exposure Coefficient (Ce)	1
Thermal Coefficient (Ct)	1

4.18 Ice Data

IS EN 1991-1-3:2003 “Eurocode 1 - Actions on structures. General actions - Snow loads (+AC:2009) (+A1:2015) states:

***(8) This Part [of Eurocode 1] does not give guidance on specialist aspects of snow loading and Ice data, for example**:*

1. *impact snow loads resulting from snow sliding off or falling from a higher roof.*
2. *the additional wind loads which could result from changes in shape or size*
3. *of the construction works due to the presence of snow or the accretion of ice.*
4. *loads in areas where snow is present all year round.*
5. *ice loading.*
6. *lateral loading due to snow (e.g., lateral loads exerted by drifts);*
7. *snow loads on bridges.*

As IS EN 1991-1-3:2003 does not give guidance on ice loading and is deemed not a consideration in the Irish Standards, the consideration of ice loading is not a design requirement for the project.

4.19 Metocean Data

Table 4-18 Tide Levels

Parameter	Levels* (m)	
	Cobh – Cork (Chart Datum)	Cobh –Cork (Malin Head Datum*)
Highest astronomical tide, m	+4.4	+1.84
Mean high water spring, m	+4.1	+1.54
Mean high water neap, m	+3.2	+0.64
Mean sea level, m	+2.2	-0.36
Mean low water neap, m	+1.3	-1.26
Mean low water spring, m	+0.4	-2.18
Lowest astronomical tide, m	-0.10	-2.66

Notes:

** Admiralty Tide Tables, United Kingdom and Ireland, NP201B, Volume 1B, 2021, UK Hydrographic Office - These levels refer to m above Chart Datum which is 2.56 m below OD Malin Head at Cobh respectively*

4.20 CO_2 Transport and Storage Infrastructure

The CO_2 is liquified and transported via a CO_2 carrier (marine vessel) from cryogenic intermediate storage tanks. Cryogenic CO_2 pipeline would run from the intermediate storage tanks along a new jetty to the jetty head where it would be discharged via cryogenic loading arm into visiting CO_2 carrier.

It is expected that initial operation with relatively low export throughput would start with smaller ship sizes of 7,500 m^3 and cargo transfer rate of 800 t/hr of liquid CO_2 under medium pressure conditions. Larger ship size of 15,000 m^3 may be required as export throughput increases. Table 4-19 provides the analysis for ship size of 7,500 m^3 and 15,000 m^3.

CO_2 transport and storage facilities at Cork will be designed to cater to ship size of 7,500 m^3 with partial investment as discussed below to cater to ship sizes of 15,000 m^3.

1. Storage capacity and loading lines at Cork will be sized based on ship size of 7,500 m^3. Storage capacity is based on 3 days production + parcel size of 7,500 m^3. Plot space will be kept for additional storage capacity required for ship size of 15,000 m^3 + 3 days of production.
2. Exisiting BOG compressor package for ship size of 7,500 m^3 with design margin would be adequate for ship size of 15,000 m^3.
3. Plot space will be provided for one additional loading pump required to cater to ship size of 15,000 m^3.
4. Plot space will be provided for 2 additional loading arms required for ship size of 15,000 m^3.

Table 4-19 Ship Data

Parameter	Value	Value
Ship Size, m^3	7,500	15,000
Ship loading rate, t/hr	800	16,00
Number of loading arms (minimum)	2	4
Export throughput (MMtCO2/year)	1.25	1.25
Total Distance (nautical mile)	900	900
Total ships required per year	151.5	75.8
Estimated round trip travel time, days	6.9	6.9
Inter arrival period, days	2.3	4.6
Storage Buffer, production days	3	3
Storage capacity, m^3	18,550	26,050

5 PHILOSOPHY DOCUMENTS

The philosophy documents that will be developed as part of pre-FEED study are:

- Process and Utilities Design Philosophy
- Process Control and Safeguarding Philosophy
- Pipeline Design Philosophy
- Material Selection Philosophy
- Flow Assurance Philosophy
- Marine Design Philosophy
- Health, Safety, Security and Environment Philosophy
- Operations and Maintenance Philosophy
- Process Safety Design Basis
- Power Generation and Electrical Systems Philosophy
- Controls and Communication Philosophy
- Stakeholder Management Philosophy
- Legislative Approvals Philosophy
- Project Execution Plan
- RAM (Reliability, Availability, Maintainability) Study

Appendix A
Units of Measurement

UoM for PFD, Heat Material Balance and Stream Summary

Parameter	UOM	Remarks
Flowrates of vapours, gases, steam, liquids, catalyst and solids	tonnes / hr or kg/hr or MMtpa;	
System Pressure	bara, barg	
Vacuum	mm Hg abs	
Delta P	mm Hg / bar	
Temperature	deg C	
Level	% Vol.	Non-linear level control shall be used wherever applicable.

UoM for Datasheets, Specifications, Design Documents and Drawings

Parameter	Unit of Measurement				
SPACE AND TIME					
Length	m	mm			
Area	m^2	mm^2			
Volume	m^3	l (litre)	ml		
Time	s	hr	day		
Velocity	m/s	mm/s			
Acceleration	m/s^2				
Volume Flow	m^3/s	l/s	ml/s	m^3/h	m^3/d
Plane angle	rad	degree	minute	second	
Solid angle	sr				
Angular velocity	rad/s				
PERIODICITY					
Frequency	MHz	kHz	Hz		
Rotational frequency	rev/s	rpm			
MECHANICS					
Mass	t (tonne)	kg			
Mass Flow	t/hr		kg/hr	MMtpa	
Molar Flow	kgmol/h		kgmol/s		
Volumetric Flow	m^3/hr				
Normal Volumetric Gas Flow	Nm^3/hr	(0^oC and 1.013 bara)			
Standard Volumetric Liquid Flow	Sm^3/hr	(15^oC)			
Density	kg/m^3				

Liquid Absolute Density	kg/m^3	(15^{o}C)			
Momentum	kgm/s				
Moment of inertia	kgm^2				
Force	N				
Moment of force	Nm				

Pressure (Absolute)	bara	mmHgA			
Energy, Work	MJ	kJ	kJoules		
Power	MW	kW	W		
Dynamic Viscosity	cP (centipoise)	Pa s			
Kinematic Viscosity	cSt (centistokes)	m^2/s			
Surface Tension	dyne/cm				
Conductivity	µS / cm				
Sound Pressure	dB				

HEAT

Absolute temperature	K				
Customary temperature	^{o}C				
Heat Quantity	kJoules				
Heat flow rate	kJoules/hr				
Density of heat flow rate	kJoules/m^{2}hr				
Thermal conductivity	Watt/m-K				
Coefficient of heat transfer	kJoules/hr m^2 □C				
Specific heat capacity	kJoules/kg-^{o}C				
Specific entropy	kJoules/kg				
Calorific value (mass basis)	kJoules/kg				
Specific energy, specific enthalpy, specific latent heat	kJoules/kg				
Calorific value (volume basis)	kJoules/Sm^3				

ELECTRICITY AND MAGNETISM

Electric current	kA	A	mA		
Electric charge, quantity of electricity	kC	C	µC		
Electric potential and electromotive force	kV	V	mV	µV	
Electric field strength	V/m				
Capacitance	F	µF	pF		
Current density	A/mm^2		A/m^2		
Magnetic field strength	A/m				
Magnetic flux	Wb	mWb			
Magnetic flux density	T				
Self inductance, mutual inductance	H	mH	µH		
Permeability	H/m				
Resistance, impedance, reactance	MΩ	kΩ	Ω	mΩ	µΩ
Conductance	kS	S	mS	µS	
Resistivity	Ωm	µΩm			
Active power	MW	kW	W		

Reactive power	MVAr	kVAr	VAr		

Apparent Power	MVA	kVA	VA		
Electrical energy	MWh	Wh	MJ	kJ	J

ILLUMINATION	
Luminous intensity	Cd
Luminous flux	Lm
Illumination	Lx
Luminance	cd/m^2

Notes:

- *Millimeter (mm) shall be used for piping system sizing.*
- *Standard conditions are 15°C and 1.013 bara.*
- *Normal conditions are 0°C and 1.013 bara.*
- *Conditions for specific gravity are T°C / 15°C.*